

SECTION 00530

BID

Via Email to: Brian Jaruszewski (bjaruszewski@tridamproject.com)

In response to your call for bids, the undersigned (also referred to as “Bidder”) having examined the site of the Work, the Contract Documents, Contract Drawings, and documents attached thereto, or other documents that are otherwise implied, hereby proposes to furnish the labor, all equipment, all materials, all devices and other costs including federal, state, county and local sales or other taxes, to do the work for which prices are quoted below, and to complete all work ready for use within the number of working days specified and in accordance with said Contract Documents. The Bidder further agrees that at least thirty-three percent (33%) of all labor will be self-performed by the bidding Contractor.

Schedule of Baseline Bid Prices

The following Schedule of Bid Prices shall constitute the Bidder’s price for Work. In the following Bid, amounts shall be shown in figures for the bid items. The total base Bid Price shall be shown in both words and figures. In case of discrepancy between the words and figures, the words will govern.

Unit Quantities

The OWNER reserves the right to adjust unit quantities to greater or lesser than twenty-five percent (25%) of the estimated quantities without change to the Contractor’s Bid Unit Price.

TRI-DAM PROJECT – Tulloch Day Use Site Project					
Schedule of Bid Prices					
Bid Item	Bid Item Description	Estimated Quantity	Unit	Unit Price	Unit Price Extension
ON-SITE					
A. Site Work					
A1	CLEAR AND GRUB	1	LS	\$	\$
A2	EXCAVATION	175	CY	\$	\$
A3	FILL MATERIAL	1	LS	\$	\$
A4	COMPACT ORIGINAL GROUND	8,085	SF	\$	\$
A5	CONCRETE SUBGRADE COMPACTION	4,582	SF	\$	\$
A6	0.2' ASPHALT CONCRETE	120	TON	\$	\$
A7	0.35' AGGREGATE BASE	210	TON	\$	\$
A8	CONCRETE FLAT WORK	4,582	SF	\$	\$
A9	CONCRETE CURB	87	LF	\$	\$
A10	CONCRETE CURB AND GUTTER	165	LF	\$	\$
A11	STAIRS COMPLETE (WITH HANDRAILS)	1	LS	\$	\$
A12	ADA RAMP (WITH HANDRAILS)	1	LS	\$	\$
A13	EMERGENCY ACCESS GATE	1	EA	\$	\$
A14	STRIPING	1	LS	\$	\$
A15	"BEWARE GATE OPENS INWARD" SIGN	1	EA	\$	\$
A16	PEDESTAL KEY PAD (WITH 4 BOLLARDS)	1	EA	\$	\$
A17	HANDRAIL NEAR RESTROOM	1	LS	\$	\$
A18	TIRE STOP	17	EA	\$	\$
A 19	STRIPING	1	LS	\$	\$

TRI-DAM PROJECT
TULLOCH DAY USE SITE
CALAVERAS COUNTY, CALIFORNIA

A20	"NO PARKING" SIGN	1	EA	\$	\$
A21	"SLOPE OF GANGWAY MAY VARY WITH CHANGE IN WATER LEVEL" SIGN	1	EA	\$	\$
A22	ADA COMPLIANT SIGNAGE PER C.B.C. 11B-703.7.2.1	1	EA	\$	\$
A23	ADDRESS SIGN	1	EA	\$	\$
A24	GATE MOTORS	2	EA	\$	\$
A25	14' SWING GATE	2	EA	\$	\$
A26	5' TALL FENCE	312	LF		
A27	GATE STOP	2	EA	\$	\$
A28	TRAFFIC LOOPS (COMPLETE)	1	LS	\$	\$
A. Subtotal Site Work					\$ _____
B. STORM DRAIN					
B1	DROP INLET CATCH BASIN	1	EA	\$	\$
B2	YARD INLET DRAIN	1	LS	\$	\$
B3	12" STORM DRAIN	56	LF	\$	\$
B4	8" STORM DRAIN	64	LF	\$	\$
B5	RIP RAP	1	LS	\$	\$
B6	GRADE LOWER TERRANCE AREA TO DRAIN	1	LS	\$	\$
B7	EROSION PROTECTION	1	LS	\$	\$
B Subtotal Storm Drain					\$ _____

C. SANITARY SEWER					
C1	CONNECT TO EXISTING FORCEMAIN	1	LS	\$	\$
C2	2" CHECK VALVE	2	EA	\$	\$
C3	2" SSFM	16	LF	\$	\$
C4	4" SEWER	2	LF	\$	\$

C5	SANITARY SEWER CLEAN OUT	1	EA	\$	\$
C6	SANITARY SEWER LIFT STATION (COMPLETE)	1	LS	\$	\$
C. Subtotal Sanitary Sewer					\$ _____

D. OFFSITE SEWER					
AD1	Alternate 1				
	Connect to existing sewer line, which is currently capped onsite, and which currently connects to adjacent properties located at 7340 and 7360 shall be field verified using Sewer TV equipment to survey integrity. File report with District prior to connecting. All work to conform to CCWD standards.	1	LS	\$	\$
AD2	Alternate 2				
	In addition to AD1, install a slip line along the length needed to obtain CCWD approval for connection. Approximately 600' All work to conform to CCWD standards.	600	LF	\$	\$
AD3	Alternate 3				
	Install a sewer service lateral (minimum of 2" in size) from the edge of property to the nearest available connection point – a sanitary manhole approximately 600' from the proposed waste tank installation point, crossing easements onto adjacent properties and County permits may be required. A cleanout may also be required at a possible choke point in	1	LS	\$	\$

	field. CCWD Design and Construction standards are to be followed during construction. Construction material shall be submitted to the District for approval before installation.				
D. Subtotal Offsite Sewer					\$ _____

E. WATER					
E1	CONNECT FOR EXISTING WATER (8" X 2" X 8" TEE)	1	LS	\$	\$
E2	2" WATER	62	LF	\$	\$
E3	2" METER	1	EA	\$	\$
E4	2" GATE VALVE	2	EA	\$	\$
E5	BACK FLOW PREVENTER ASSEMBLY	1	EA	\$	\$
E6	3/4" WATER	10	EA	\$	\$
E7	3/4" GATE VALVE	1	EA	\$	\$
E8	2" CAP	1	EA	\$	\$
E9	RELOCATE EXISTING WATER METER	1	LS	\$	\$
E. Subtotal Water					\$ _____

F. OFFSITE WATER					
F1	Extend new 6" water main to the 8" water main at APN 064-029-036 (approximately 600') to connection point from edge of property following CCWD District Design and Construction Standards. A set of approved Engineering Plans for the line extension shall be provided prior to line installation.	1	LS	\$	\$
F. Total Offsite Water					\$ _____

G. RETAINING WALL					
G1	CMU SCREEN WALL (COMPLETE AS SHOWN)	1	LS	\$	\$
G2	STACKED ROCK WALL (COMPLETE AS SHOWN)	1	LS	\$	\$
G3	REFURBISH SEA WALL (COMPLETE AS SHOWN EXCEPT OMIT SLURRY)	1	LS	\$	\$
G. Subtotal Retaining Wall					\$ _____

H. MISCELLANEOUS					
H1	PICNIC TABLE WITH SHADE STRUCTURES (COMPLETE)	5	EA	\$	\$
H2	PROVIDE ENGINEERING AND RELOCATE FISHING PIER, INCLUDING LOW WATER SUPPORTS	1	LS	\$	\$
H3	PROVIDE ENGINEERING AND INSTALL GANGWAY WITH HANDRAIL AND ATTACH TO CONNECTION AT SHORELINE	1	LS	\$	\$
H4	INSTALL ALL ADA PARKING SIGNAGE	1	LS	\$	\$
H5	PRE-FABRICATED BATHROOM (COMPLETE AND INSTALLED)	1	LS	\$	\$
H6	ALL LANDSCAPING AND IRRIGATION COMPLETE (PER LANDSCAPING PLAN)	1	LS	\$	\$
H7	ALL ELECTRICAL WORK COMPLETE (PER THE ELECTRICAL PLAN)	1	LS	\$	\$
H. Subtotal Miscellaneous					\$ _____

TRI-DAM PROJECT
TULLOCH DAY USE SITE
CALAVERAS COUNTY, CALIFORNIA

I. OFF-SITE					
1	CLEAR AND GRUB	1	LS	\$	\$
2	EXCAVATION	15	CYD	\$	\$
3	FILL MATERIAL INCLUDING FEATHERING SHOULDERS	1	LS	\$	\$
4	COMPACT ORIGINAL GROUND	1855	SF	\$	\$
5	SAW CUT	155	LF	\$	\$
6	0.2' ASPHALT CONCRETE	28	TON	\$	\$
7	0.35' AGGREGATE BASE	48	TON	\$	\$
8	12" AC DEEP LIFT	12	TON	\$	\$
9	CLASS 1 FLEXIBLE POST DELINEATOR	1	LS	\$	\$
10	"NO PARKING" SIGNS	2	EA	\$	\$
11	PEDESTAL KEY PAD (WITH 4 BOLLARDS)	1	EA	\$	\$
	OFF-SITE TOTAL				\$

Subtotal – Items A through I		
A.	SITE WORK	\$
B.	STORM DRAIN	\$
C.	SANITARY SEWER	\$
D.	OFFSITE SEWER	\$
E.	WATER	\$
F.	OFFSITE WATER	\$
G.	RETAINING WALL	\$
H.	MISCELLANEOUS	\$
I.	OFF-SITE	\$
	BID TOTAL "A-H" ON-SITE	\$
	BID TOTAL "I" OFF-SITE	\$
	TOTAL ON-SITE AND OFF-SITE	\$
	Total Bid Price TDP Tulloch Day Use Site (in words) <hr/> <hr/>	

Note: All work shown on the plans or implied on the plans shall be included in the final cost.

Narrative of Bid Item Description Listed Above – (Schedule of Bids)

A narrative of the primary bid items is provided for the convenience of the Bidder. The narrative is not all-inclusive of the Work to be performed and does not replace or negate any Work required in the Contract Documents or accompanying Project Drawings. All other work required to complete the Contract Documents is considered incidental and not subject to payment.

A. Mobilization and Demobilization

Mobilization and Demobilization generally consists of work associated with Section 01400 Mobilization and Demobilization, Section 01500 Temporary Facilities of the Contract Documents and is not to exceed 5% of the total bid price. Related Work may include work associated with Section 01700 Contract Closeout.

Bid Guaranty and Signature

Attached hereto and made a part hereof is United States Currency, Cashier's Check, Certified Check or Surety Bond No. _____ in the amount of \$_____, which is not less than ten percent (10%) of the total amount of the total Bid, as a guaranty that the Bidder will enter into a Contract in the form bound with these Contract Documents within five (5) days after the Notice-of-Award of the Contract by the OWNER.

The undersigned hereby agrees that, in case his Bid is accepted, he will within five (5) days after notice thereof, execute a Contract with the OWNER in the form hereto attached and, if required by law, shall furnish a bond in the sum of the Contract price to secure the payment of all labor and material bills, and also a bond in the sum of the Contract price to secure the faithful performance of the Contract according to the terms and provisions therein; and in case of failure to execute the Contract and furnish the bonds within said period or such extension thereof as may be allowed by resolution duly passed and adopted, it is expressly agreed that the OWNER may award the Contract to the second lowest Bidder and the amount of Bidder's security shall be forfeited to the OWNER.

It is understood by the undersigned that the quantities of material of Work specified in the Notice Inviting Sealed Bids are estimated and are given only for the purpose of comparing Bids and that the prices quoted are not conditioned upon the accuracy or approximate accuracy of the estimate.

It is understood that the OWNER may award a Contract as the interests of the OWNER may dictate.

Attached hereto and made a part of this Bid is a list of Subcontractors as required by the provisions of Sections 4100 to 4113 of the Government Code of the State of California.

CONTRACTOR: _____

BY: _____

TITLE: _____

ADDRESS: _____

CONTRACTOR'S LICENSE NUMBER: _____

DIR REGISTRATION NUMBER: _____

TELEPHONE NUMBER: _____

- END OF SECTION 00530 -